

GYP-SPAN® Radiant Recommended Specifications

PART I. GENERAL

1.1 Scope

Specify to meet project requirements. The conditions of the Contract (General, Supplementary, and other conditions) and the General Requirements (sections of Division 1) govern the provisions of this section.

1.2 Qualifications

- A. Supplier: Hacker Industries, Inc., Newport Beach, California.
- B. Installer: Installation of GYP-SPAN® Radiant shall be by a Licensed Applicator of Hacker Industries, Inc., using mixing and pumping equipment approved by Hacker Industries, Inc.
- C. All materials specified herein shall be approved by Hacker Industries, Inc., Newport Beach, CA. All others must receive prior approval.
- D. Compressive strength should be specified from 2000 to 3200 psi (approx. 13.8 to 22.1 MPa).
- E. Materials shall be delivered in their original, unopened packages, and protected from exposure to the elements after delivery. Do not allow bags to get wet.
- F. Certification: Upon completion of this portion of the work, and as a condition of its acceptance, deliver to the architect a certificate from Hacker Industries, Inc., and signed by the Licensed Applicator, stating that the material used in this work complies with the specified requirements.

PART II. PRODUCTS

2.1 Materials

- A. Gypsum Concrete: GYP-SPAN® Radiant, as supplied by Hacker Industries, Inc.
- B. Subfloor Primer: Hacker Floor Primer or approved equal
- C. Sand: 1/8" (3mm) or less washed plaster or masonry sand
- D. Water: Potable and free from impurities
- E. Hacker TopCoat™ SP, if specified

2.2 Mix Designs: *see section 3.3*

PART III. PREPARATION

3.1 Condition of Subfloor

- A. Subfloor must be structurally sound (L/360), broom clean, dry, and free from oil, grease, paraffin, laitance or other contaminants before the arrival of the Hacker Licensed Applicator.
- B. Leak Prevention: All cracks and voids should be filled with a quick-setting patching or taping compound or equal where leakage could occur.
- C. Before installation, the General Contractor shall inspect and approve the condition of the subfloor and test for dryness.

3.2 Priming

- A. Prime wood subfloors with one coat of Hacker Floor Primer (diluted 1:4 with water) using one gallon of Hacker Floor Primer (approx. 3.78L) per 500 sq. ft. (approx. 47m²).
- B. Hacker Floor Primer is not always required over concrete substrates. Multiple coats may be required over porous concrete or plank. The Hacker Licensed Applicator can give specific recommendations. (Note: for rehabilitation work or pours over old and/or porous concrete, consult a Licensed Applicator or Hacker Industries, Inc., for recommended floor preparation.)

3.3 Mixing Instructions

- A. 4 to 6 gallons (approx. 15.1 to 22.7L) of water and sand per 80 pound (approx. 36.3 kg) bag of GYP-SPAN® Radiant. Do not over water. Water amount will change with wetness of sand.
- B. GYP-SPAN® Radiant mix proportions and methods shall be in strict accordance with Hacker recommendations.

3.4 Underlayment Application

- A. Scheduling:
 - 1. Installation of GYP-SPAN® Radiant shall not begin until the building is enclosed, including roof, windows, doors and other openings.
 - 2. GYP-SPAN® Radiant can be installed before or after the installation of drywall as specified.
- B. Application:
 - 1. The minimum thickness of GYP-SPAN® Radiant varies with the type of radiant tubing. Install the first lift (pour) to the top of the tubing or cable. After the first lift has set-up, install the second lift (pour) 3/4" (19mm) above the first lift. The minimum thickness of GYP-SPAN® Radiant is 3/4" (19mm) over the top of the tubes or cables.
 - 2. Install GYP-SPAN® Radiant at specified thickness by placing bags, sand and water into the approved high-speed mixing device and blend for a minimum of one minute. GYP-SPAN® Radiant should be pumped onto

floor areas, spreading and screeding to a smooth surface. Place as continuously as possible until installation is complete so that no GYP-SPAN® Radiant slurry is placed against GYP-SPAN® Radiant that has obtained its initial set, except at authorized joints.

3. GYP-SPAN® Radiant is suitable for interior applications only and must be covered by a finished floor material.
- C. Protection: After installation, temporary wood planking shall be placed by General Contractor wherever the floor underlayment will be subject to wheeled or concentrated loads.
- D. Drying: Before, during and after installation of GYP-SPAN® Radiant, building interior must be ventilated and heated to a minimum 50°F (10°C) to assure completion of the drying process. The General Contractor shall provide continuous ventilation and adequate heat to rapidly remove moisture from the area until the GYP-SPAN® Radiant is dry. Do not install finished floor coverings until the GYP-SPAN® Radiant has been tested for dryness. Consult flooring contractor for recommended procedures to test for dryness. Reference Hacker Industries, Inc.'s Drying Conditions Flyer.

3.5 Preparation For Installation of Floor Coverings

- A. Sealing: Any areas where the underlayment surface has been damaged should be cleaned and sealed regardless of floor covering specified. Floor covering manufacturers' specifications and requirements supersede these recommendations.
- B. Floor Covering Procedures: Please see the Hacker Industries, Inc.'s "Guidelines for Installing Finished Floor Coverings". The guideline is not a warranty and should be used as a guideline only. Also see ASTM F2419 for recommended procedures.

3.6 Field Quality Control

- A. Slump Test: GYP-SPAN® Radiant shall be tested for slump at the beginning of each installation in order to establish the required slump. Slump tests shall then be taken periodically during installation to verify that the required slump is maintained. Slump tests shall be conducted using a 2" by 4" (approx. 51mm by 102mm) cylinder. The acceptable patty size should be 7-1/2" (approx. 191mm) plus or minus 1/2" (approx. 13mm) in diameter.
- B. Field Samples: Testing shall be done in accordance with ASTM modified C472 testing procedures, using 2" (approx. 51mm) split brass molds. Prior to independent sampling, contact Hacker Industries, Inc., to ensure that proper ASTM procedures are followed. If requested prior to installation, test results shall be available to the architect and/or contractor from the Licensed Applicator.