

Post-Pour Instructions



Firm-Fill[®]
Gypsum Underlayments

**After installation of the FIRM-FILL[®] Underlayment,
the general contractor is responsible for the following:**

1. Provide adequate ventilation and heat to assure completion of the drying process (above 50° F [10° C]).
2. Optimum drying time is 10-14 days.
3. Prior to the installation of finished floor goods and/or any sealer, the underlayment must be free of any moisture. Consult your flooring contractor for recommended test for dryness.
4. Temporary wood planking must be placed wherever the underlayment will be subject to heavy wheeled or concrete loads during the curing period.

Project Name: _____

Date(s) of Pour: _____

Licensed Applicator: _____

Phone Number: _____

**FIRM-FILL[®] Brand Gypsum Underlayments have added the following
benefits to your floor/ceiling assembly:**

- **Improved Sound Control**
- **High Compressive Strengths**
- **Rock-Solid, Flat Surface**
- **UL Rated Fire Resistance**
- **Durability**
- **Contributes to LEED**

If you need additional information, please contact your Licensed Applicator at the number above, or call Hacker Industries, Inc. at (800) 642-3455 | HackerIndustries.com